
Project: LIVERMORE, CA 94550 page: 1 of 2


Date: <u>8/31/2012</u> Engineer: <u>XXX</u>

## **HYDROTHERM KN-2 BOILER SEISMIC ANCHORAGE (ASCE 7-05)**


### **Slab on Grade Applications Only**

#### **Equipment Parameters:**





#### Seismic Parameters:



$R_p =$	2.500	(Default value for Anchorage per ASCE 7-05 Table 13.6-1)
$F_a =$	1.000	(ASCE 7-05 Table 11.4-1)
$S_{MS} = F_a * S_s =$	1.798	(ASCE 7-05 Eqn. 11.4-1)
$S_{DS} = 2/3*S_{MS} =$	1.199	(ASCE 7-05 Eqn. 11.4-3)

Seismic Design Category = D

### Seismic Force:

Project: LIVERMORE, CA 94550

Date: 8/31/2012 Engineer: XXX


# **HYDROTHERM KN-2 BOILER SEISMIC ANCHORAGE (ASCE 7-05)**

### **Design Anchorage Force:**

Horizontal Shear Force Per Anchor:

$$R_H = F_p/4 =$$
 61.8 LBS.

## Overturning Resistance About Point A:



$$x = 14.66$$
 in.  $x = lesser of L or W$ 

page:

2 of 2

$$M_{OT} = F_p^* cg =$$
 **564.1** LBS.-FT.

$$M_{RES} = W_p^* x/2 =$$
 336.0 LBS.-FT. Uplift

Vertical Acceleration: assume  $\rho = 1.0$ 

Ev = 
$$\rho^* Fp + 0.2^* S_{DS}^* W =$$
 193.7 LBS. (ASCE Section 13.3.1)

$$R_{VNETUP} = (M_{OT}/(2*x))-(W_p/4)+(Ev/4) =$$
 0.0 LBS. No Uplfit

### Force Summary Per Corner:

#### Component Anchorage:

$$R_{HNET} =$$
 61.8 LBS.  $R_{VNETUP} =$  0.0 LBS.

### Anchors Embedded in Concrete or CMU:

$$1.3^*R_p^*R_{HNET} =$$
 **200.9** LBS.   
  $1.3^*R_p^*R_{VNETUP} =$  **0.0** LBS.