





MADE IN THE USA


HIGH CAPACITY BASEBOARD RADIATION

## **Petite**<sup>6</sup>

## RATINGS

MODEL	GPM	AVERAGE HOT WATER TEMPERATURE - BTU/HR./LIN. FT.						
		120°F	130°F	140°F	150°F	160°F	170°F	180°F
P9 3/4"	4	308	386	470	560	650	750	850
	1	292	366	445	530	620	710	800
P9 1"	4	297	373	454	540	630	730	820
	1	281	352	428	510	600	690	780

NOTES: All the ratings noted include a 15% addition for heating effect. These ratings are based on active length, which is total length less 4 1/2". Pressure drop for element with nominal 3/4" copper tube is 0.47 inches of water per linear foot at 1.0 GPM and .525 inches at 4.0 GPM. Pressure drop for element with nominal 1" copper tube is 0.13 inches of water per linear foot at 1.0 GPM and .145 inches at 4.0 GPM. The use of ratings at 4.0 GPM is limited to installations where the water flow rate through the baseboard unit is equal to or greater than 4.0 GPM. Where the water flow rate through the baseboard is not known, the rating of 1.0 GPM must be used.



DESCRIPTION CAT. NO. PER CARTON P9-REC 4" End Cap - Right Hand Hinged 12 4" End Cap - Left Hand Hinged P9-LEC 12 3" Solid End Cap, Right P9-3REC 10 P9-3LEC 3" Solid End Cap, Left 10 4" Solid End Cap, Right P9-4REC 8 P9-4LEC 4" Solid End Cap, Left 8 P9-IC 90° Inside Corner 12 135° Inside Corner P9-ICB AS ORDERED 90° Outside Corner P9-OC 10 135° Outside Corner P9-OCB AS ORDERED 2" Panel Joiner (3 pcs) P9-PJ3 AS ORDERED 4" Wall Trim to Floor P9-WJ 12 **Element Slide Cradle** P9-ESC AS ORDERED Support Bracket + Nylon Cradle P9-BR AS ORDERED P9-STH AS ORDERED Supply Tube Hanger (lower) Return Tube Hanger (upper) P9-RTH AS ORDERED 14" Filler Piece Set P9-FIS AS ORDERED Touch-Up Spray Paint P9-TUP 6

ELEMENT CARTON NO. ASSEMBLED BASEBOARD SPECIFY Model P9CU75 complete assembled P9CU75-8 units (single pack) include one length P9CU75-7 each of back panel, front panel, P9CU75-6 damper-louver and 3/4" heating 3/4" CU P9CU75-5 element, 18 GA. front panel, plus P9CU75-4 required support brackets and element P9CU75-3 cradle expansion clips. Panel joiner P9CU75-2 included with 5', 6' & 8' lengths. Model P9CU100 complete assembled P9CU100-8 units (single pack) include one P9CU100-7 length each of back panel, front P9CU100-6 panel, damper-louver and 1" heating 1" CU P9CU100-5 element, plus required support P9CU100-4 brackets and element cradle P9CU100-3 expansion clips. Panel joiner included P9CU100-2 with 5', 6', & 8' lengths.

Model P9CO enclosure only assembled (single pack)P9CO-8 P9CO-718GA. includes one length each of back panel, front panel, damper-louver plus required support brackets. Panel joiner included with 5', 6' & 8' lengths.P9CO-3 P9CO-3	ENCLOSURE ONLY	PACKING	SPECIFY
	assembled (single pack) 18GA. includes one length each of back panel, front panel, damper-louver plus required support brackets. Panel joiner	ASSEMBLED	P9CO-7 P9CO-6 P9CO-5 P9CO-4 P9CO-3

ELEMENT ONLY	ELEMENT SIZE	CARTON NO. SPECIFY
E75 3/4" CU tube elements only elements and cradles individually boxed.	3/4" CU	E75-8 E75-7 E75-6 E75-5 E75-4 E75-3 E75-2
E100 1" CU tube elements only, elements and cradles individually boxed.	1" CU	E100-8 E100-7 E100-6 E100-5 E100-4 E100-3 E100-2

Petite<sup>(</sup>

260 North Elm Street, Westfield, MA 01085 (413) 564-5545 · FAX (413) 572-3764 7555 Tranmere Drive, Mississauga, Ontario, L5S 1L4 Canada (905) 670-5888 · FAX (905) 670-5782 www.sterlingheat.com

